


Monticello Nuclear Generating Plant



Plant Process Computer System Replacement Russ Van Dell, True North Consulting Curtiss-Wright Symposium, August, 2018



Minnesota

- Last Year, the New York Times stated that "After having dug to a depth of 10 feet, a team of New York scientists found traces of copper wire dating back 100 years. They came to the conclusion that their ancestors already had a telephone network more than 100 years ago."
- Not to be outdone by the New Yorkers, in the weeks that followed, California archeologists dug to a depth of 20 feet and the Los Angeles Times wrote "California Archeologists report finding of 200 year old Copper wire, have concluded that their ancestors had an advanced communications network more than 200 years ago"
- One week later, a local Minnesota newspaper reported that "After digging to a depth of more than 30 feet in his pasture near Twig, Minnesota, Ole Svenson, a self taught Archeologist, reported that he found absolutely nothing. This led Ole to conclude that more than 300 years ago"

Minnesota had already gone "Wireless".

Minnesota Proud!




Monticello Nuclear Generating Plant

- Xcel Energy (Minnesota, N & S Dakota, Wisconsin, Michigan, Colorado, New Mexico, Texas)
 - Largest Wind Producer
 - **80% Carbon Free by 2030 (with Nuclear Plants)**
- Monticello, Minnesota
- □ GE BWR3
- □ First On-Line 1971
- **□** 691 Mega-Watts
- □ Plant Life Extension to 2031




MNGP PPCS Migration – Original GEPAC+






MNGP PPCS Migration – 2002 Decision





MNGP PPCS Migration – 2002





PPCS Migration 2007-2013– Expand C3TREK

- Plant projects priority over PPCS replacement
- Old DAS system not expandable obsolete
- Support projects using C3Trek system as base system

High Priority Multiple Plant upgrades


- ISFSI
- Crossflow Project (MUR/FW loss recovery)
- Cyber Security Data Diodes

Extended Power Uprate

- Power Range Neutron Monitors (PRNM)
- Bentley Nevada Vibration Monitoring
- Met Tower/RASCAL/Chemistry
- 13KV, Transformers, RFP/CDP, Recirc MG Sets, Turbine
- MELLA+



Current Configuration Hybrid - GE GEPAC+ (1984) & C3-llex C3TREK (2006)— March, 2016





723 - 1R TRANSFORMER CNTMT RPV RAD **30.1** PSI TOP OIL **250.0** °C TANK PRESSURE AMBIENT TEMP **125.0** °⊂ 600 AMPS LTCX LTCY 250.0 250.0 **250.0** HS TEMP °C 115KV XFMR °C °C CONCENTRATIONS **X WINDING** Y WINDING 3000.1 PPM **ACETYLENE** 3000.1 PPMH2 VOLTS **17950 5250** VOLTS 02 25000 PPM N2 **100000** PPM **2000** AMPS AMPS **4000 METHANE** 7000 PPM **TDCG** 33000 PPM HS TEMP °C **250.0** 250.0 HS TEMP °C MOISTURE (%RS) 100.1 CO **10000** PPM **ETHANE 5000** PPM MOISTURE **80** PPM TOTAL POWER 60.05 MW ETHYLENE 5000 PPM CO2 30000 PPM MONTICELLO 4/18/2013 9:06:48 AM QA-MTAS11 723.00



MNGP PPCS Replacment –C3ilex CTREK Option

- MNGP had implemented C3-ilex's C3-TREK system
- Graphics System based on OSI-PI
- DASie Alternate to GE MVD, NIC (later)
- ATIP, RWM, PRNM implementation based on DASie design
- OD1 TIP processing C3-ilex Gardel no TIP processing
- RTP 2000 Interface based on DASie design
- Analogics support part of DASie design
- □ C3TREK calculations, interfaces
- **□** Low cost, off-the-shelf technologies



MNGP PPCS Replacement Timeline

- June, 2015 C3-ilex decided to shutdown business
- August 2015 RFP Proposal issued to vendors for alternate approach
- December 2015 Contract awarded to Curtiss Wright to replace GEPAC+ and C3-ilex C3-TREK systems
- November, 2016 Contract awarded to GE GE LINK
- 2017-2018 DAS Implementation & R*Time Design
- April, 2019 FAT
- September, 2019 Completion




MNGP Project Approach - DAS

- Project split to 2 parts Hybrid Architecture
 - DAS- Convert from Analogic to RTP 3000 (Xcel Energy)
 - PPCS Replace GEPAC and C3TREK (Curtiss-Wright,GE)
- DAS Implementation -off-line (RFO) Critical Control Panels
 - ☐ Critical Control Panels (HWC, Off-Gas, Safety Instruments
 - □ PPCS Digitals 450 pts Used CW plug in adapter Analogic to RTP
- DAS on line in plant Rx Bldg Chemistry
- DAS on line Computer Room Challenging
 - □ Control system interfaces (some high risk) Plant knowledge
 - Critical Points special handling
 - □ Calculations
 - □ Interfaces (Maintain 100% Power)



DAS Replacement – EC-14189 DAS to new hardware






MNGP Project Approach – PPCS Challenges

- PPCS Replace GEPAC and C3TREK
- Replacement done with unit on-line no capacity losses
- Knowledge, Documentation, Complexity, Size
- OD-1 TIP Processing new to R*Time, part of 3DMonicore
- NUMAC & Analogic Interface C3-ilex DASie
- □ Calculations GEPAC Scheduler versus R*TIME
- TRA speed Analogics (4msec Analog)
- 10ohm RTDs Noise RTP
- Interfaces Complex, Different technologies
- Funding EPU consumed all Capital investment







MNGP Project Approach – PPCS Enhancements

- PVQ Point Manual Insert both Value & Quality
- Instrument Calibration
 - Remove Instrument from Processing (Manual Entry or not)
 - I&CS views live instrument input for cal purposes
- R*TIME version 15
 - □ Change Track Archive GEPAC Delta Processing
 - Enhancements
- Scram Time Application
 - Scram Time data obtained from RWM
 - Calculations performed
 - □ Results on Graphic Display
 - □ Track Progress of Single Rod Scrams
 - □ Current Status of Control Rod Operability
- □ Digital Recorders expand points, EOP abilities
- Gardel Fuel Limit Calc Results R*TIME



MNGP PPCS Enhancements - GELINK

- ☐ GE NUMAC LINK- GE's Replacement for MVD, NIC
- Input Communicates with GE's Proprietary Products Analogic, NUMAC (RWM, ATIP, PRNM)
- Output PPCS Vendor Interface
 - UDP Broadcast Mode
 - TCP Interactive communication between NUMAC & PPCS
 - Keyswitch Controls Mode (for Cyber Security)
- □ GE
 - Solid Engineering Support & Knowledge
 - GE NUMAC LINK Delivered to two other non-RTIME plants
 - □ GE NUMAC LINK Ethernet Communication Protocol Specification
 - □ Provides exact details of all communication to/from GELINK
 - Available to PPCS Vendors for use in creating interface applications
- Integration/FAT Test at GE Lab, Wilmington
- □ Hardware Based on existing NUMAC components




GE NUMAC LINK





GE NUMAC LINK Configuration




MNGP Project Resources

- Most of Project is Technical/Details/DAS Wiring
- Minimal traditional engineering
- Project Management/Engineering
- Architect Engineering not used
- Project Manager (Projects Department)
- Engineering per Internal resources (IT & Design Engineering)
 - □ Computer Engineers
 - Retired Computer Engineer (Project Lead, True North Consulting)
 - □ Retired Master Instrument & Control Specialist (field engineering)
 - □ Retired Shift Manager (procedures, work plans)
 - **□** Engineering Associate (procedures, test cases)
 - Nuclear Engineers (ATIP, Gardel, Scram Timing)
 - □ Design Engineering w/Design Change Qualifications/Calcs
 - Work Planner
- ☐ Challenge Balance between DAS & PPCS work tasks




PPCS Input Composition (3753)



DAS EC moves about 50% (1015pts) of hardwired Analog/Digital pts from Analogics (old) to RTP3000 (new).



PPCS Calculated Point Composition (2810)







Original
Honeywell
IO Cab w/
Analogic






RTP
Termination
Modules






Original
Honeywell
Drum
Cabinet









Your task as our selected Vendor



Some days we just get stuck, and bogged down. Some days all you can do is smile and wait for someone to kindly remove your butt from the hole you find it wedged into.





